

concrete construction

FEBRUARY 1958

VOL. 3, NO. 2

EDITED FOR

All who are concerned with quality, JOB PLACED CONCRETE (including prestress, tilt-up, lift slab, and thin-shell)—its production, handling, forming, reinforcing, placing, finishing, and curing; CONCRETE CONTRACTORS; GENERAL CONTRACTORS; INDUSTRIAL CONSTRUCTION AND MAINTENANCE MEN; ENGINEERS; ARCHITECTS; STATE HIGHWAY ENGINEERS; READY-MIXED CONCRETE PRODUCERS.

COPIES DISTRIBUTED 28,378

IN THIS ISSUE

4 DEVELOPMENTS IN CONCRETE PAVEMENTS

Nowhere in the entire field of construction is development work producing such fruitful results as it is in connection with concrete pavements. This article provides a fast review of some of the more significant trends which are profoundly affecting current practice.

9 BIDS SHOULD BE BASED ON KNOWLEDGE

Here's a simple, down-to-earth solution to the problem of assembling detailed, accurate cost information as a basis for future bidding. Best of all, the cost of the method is so nominal it's practically for free.

13 DIMPLED CONCRETE

An account of some interesting work recently done on the West Coast to develop rough textured surfaces for tilt-up wall panels that would discourage the attention of amateur young artists.

18 HOW TO PLACE CONCRETE ON A SLOPE

The somewhat unconventional use of a vibrating screed on a sloping floodwall may have resulted in savings of as much as 20 percent. This article tells about some of the problems that were encountered and how they were solved.

20 NEWS

23 QUESTIONS AND ANSWERS

24 EQUIPMENT, TOOLS, MATERIALS

29 LITERATURE

32 INDEX TO ADVERTISERS

HERE'S THE BIG
NEW LINE OF

Kelley


CONTRACTORS EQUIPMENT

• UP-TO-DATE DESIGNS

• CAREFULLY ENGINEERED
AND FULLY TESTED

• BUILT FOR ROUGH USE

• SPEEDS UP WORK...
SAVES MONEY



POWER TROWELS

Six models to choose from... 2 de-luxe HYDRA TROWELS, 34" and 44" sizes, with fingertip blade control... and 4 super models with manually adjusted blade pitch: 24" Kelley Bantam, 29" Kelley Boy, the popular 34" Kelley Chief and the big 44" Kelley Commander... a size for every job.



POWER TAMPERS

Self-propelled... delivering 2400 impacts a minute. Two models: 18" wide shoe, and 36" wide shoe. For packing down earth backfill to maximum density next to foundations, on road-widening jobs, around culverts and in pipeline trenches. Also for finishing black-top driveways.



COMPACTORS

The new Kelley Compactor with "Compaction Control". An entirely new machine... larger, easier operating, faster and more powerful. For compaction-floating concrete floors, for keying in tough surface hardener materials, and for bonding dry-tamp topping to a base slab.



SPACE HEATERS

What a blast! From the brand new Kelley Hot Shot Space Heaters, one delivering 125,000 Btu/Hr and the other delivering 325,000 Btu/Hr. Let 'er blow outside... work goes on inside with Kelley Hot Shots! For work on walls, floors, scaffolds and hundreds of other construction jobs.

CONCRETE CONSTRUCTION MAGAZINE

139 No. Clark St. Chicago 2, Illinois
ANdover 3-4329

WILLIAM M. AVERY
editor and publisher

JOHN M. ENGLE
co-publisher

AGATHA COTTON
distribution manager

CLARISSA McKNIGHT
product news editor

JOHN DEMLING
contributing editor

pacific coast representatives

DUNCAN A. SCOTT & CO.

Los Angeles 57
1901 West 8th St., Dunkirk 8-4151

San Francisco
85 Post Street, Garfield 1-7950

Published monthly and copyrighted© 1958 by Concrete Construction Magazine. The cover design and contents of CONCRETE CONSTRUCTION are fully protected by copyrights, and must not be reproduced in any manner or form. Subscription price: Single copies, \$1.00; \$5.00 per year (U.S.A.); \$10.00 per year (Foreign). Accepted as controlled circulation publication at Chicago, Illinois.

Kelley

MACHINE DIVISION

The Wiesner-Rapp Co., Inc.
285 Hinman Ave. Buffalo 23, N. Y.

Please send us information on Kelley products.

NAME _____
STREET _____
CITY _____ ZONE _____ STATE _____

BPA

FRANCHISE
CIRCULATION
fc

CONCRETE CONSTRUCTION

Pre-cast bridge and building construction goes up faster, safer with **P&H** truck cranes

From the placement of giant precast elements to concrete bucket work, you can do the job quicker, safer and at lower cost with P&H truck and crawler cranes. P&H machines have the genuine lifting power and extremely fine control you need to handle all types of concrete construction profitably.

Here are some of the reasons why P&H satisfies more users:

- Independent planetary boom hoist—boom lowering is always done under power
- P&H "live roller circle" for smoothest, fastest swings known
- Hydraulic controls—operator "feels" load at all times
- All welded, lattice type boom—lighter yet stronger
- P&H larger brakes give better braking action

No matter what the capacity requirements of your jobs, IT WILL PAY YOU TO SEE YOUR P&H DEALER SOON. Write for complete information.


HARNISCHFEGER

Construction & Mining Division
Milwaukee 46, Wisconsin

THE P&H LINE

Excavators: $\frac{1}{2}$ • $\frac{3}{4}$ • $1\frac{1}{2}$ • $1\frac{1}{2}$ • $2\frac{1}{2}$ • $3\frac{1}{2}$ and 4 yards
Truck Cranes: 10 • $12\frac{1}{2}$ • 15 • 20 • 25 • 30 • 35 • 45 and 60 tons

35-ton P&H 555 A-TC truck crane placing 28-ton concrete wall panels in construction of \$2½ million tannery plant.



New Developments in the Design and Construction of Concrete Pavements*

The dramatic growth in the use of concrete for pavement work is shown in this display first exhibited at the 1957 Road Show. The prototype section of concrete consists of a 10-inch thick reinforced slab of air-entrained concrete, with a sawed joint and skid-resistant surface, placed on a 4-inch thick non-pumping granular subbase.

By Gordon K. Ray

Highways & Municipal Bureau
Portland Cement Association

THE LARGE VOLUME of airfield pavement construction in the past 6 or 7 years has led to a number of important changes in construction equipment and techniques—some of which, at least, are already finding their way into general pavement practice.

High take-off and landing speeds, for example, have required a severe tightening of specification surface tolerances and grade control in order to provide the plane surface necessary for safe operation. The resulting new grade control requirements (.04 feet from grade at all points) have demanded more accurate form setting and a closer straightedge testing of forms and surface. This rolling straightedge, or hi-lo tester as it is called, can accurately detect deviations of as little as $\frac{1}{8}$ inch in 12 feet on either forms or finished concrete. This is the maximum permitted in the longitudinal direction on runways and taxiways for the Air Force today.

New finishing equipment is being built to assist contractors to meet these stricter surface tolerances and also to combine the work of the transverse finishing machine and longitudinal float to permit the elimination of one piece of equipment from the paving train. An early experimental machine

*Based on a paper presented before an engineering seminar at the U. S. Naval Construction Battalion Center, Davisville, Rhode Island.



employs a 30-foot wheel base, 2 transverse screeds and one float. It was used on 2 large projects in California and Arizona. A somewhat similar machine has been used on a number of 24-foot wide highway projects throughout the midwest during the past two seasons.

The stricter surface tolerances have required more careful use of scraping straightedges. These 12-foot long tools must be used transversely, longitudinally and even diagonally if the smoothness requirements are going to be met in both directions.

If the final straightedge testing of the finished surface reveals any high spots which exceed the specification tolerances, these must be ground down or the slab removed. One new machine for cutting off high spots has a 16½-inch wide head consisting of a series of diamond saw blades. The head can be set on the 12-foot wheel base machine so that it cuts all high spots to meet specifications.

Jet blast and high tire pressures encountered on modern airport pavements have led to better joint construction to eliminate spalls and ravelling which sometimes occurred on hand formed dummy grooves and buried premolded bituminous strips. Sawed joints* were perhaps one of the most important recent developments in concrete paving technology. When such joints are sawed in the hardened concrete at the proper time, cracking is controlled and a durable, smooth riding, attractive joint results.

The saws for cutting such joints have progressed rapidly in the last 6 years to recent self-propelled 36-horsepower machines capable of cutting joints up to 5 or 6 inches deep in the hardest coarse aggregates. Sawblades have also gone through a rapid series of improvements, both the steel diamond-tipped blades which are used in the harder coarse aggregates and the abrasive blades made of silicon carbide and reinforced with metal or fiber glass-nylon mesh. Both types of blades are available in a variety of diameters and widths, but the abrasive blade is much cheaper and has the further advantage that it can be used dry while the diamond blade must be provided with a pressure spray of cooling water. Dry sawing permits earlier sawing without ravelling or erosion in the joint, but unfortunately abrasive blades are only suitable in concrete made with the softer coarse aggregates, such



Photo courtesy Concut Sales, Inc.

High spots on finished pavements can be ground off with special bump cutters of the type shown here. The cutting head on this machine consists of a series of diamond saw blades. Two or three passes are generally necessary to plane most surfaces.

Tighter specifications on surface tolerance and grade control have led to the development of machines like this rolling straightedge which can detect deviations of as little as ¼ inch in 12 feet on finished concrete. The machine automatically dye marks slab areas which are not within specification limits.

Photo courtesy Viking Manufacturing Company



*See "Sawed Joints," *Concrete Construction*, January 1958, page 3.



View of a modern slip-form paving machine at work on a highway project in Iowa. Finishers with straightedges and floats do final surface finishing behind paver, but inside traveling forms.

as limestone, slag and coral.

Two new modifications of sawed joints have been developed in an effort to reduce the cost of sawing in hard aggregates and permit earlier sawing to insure positive crack control. One requires using a special machine which vibrates a transverse bar made of perforated metal into the concrete surface at the exact joint location to displace the coarse aggregate. As the still vibrating bar is removed from the concrete, mortar only flows back into the groove created. The surface is then straightedged, and at the proper time, a joint is sawed at the same location. The displacement of the hard coarse aggregate permits the use of an abrasive blade and results

in tremendous sawing economy.

The second modification involves the insertion of an asphalt-impregnated felt board of the proper dimensions at the joint location. The surface over the strip is then straightedged and finished in the conventional manner. This strip, which creates a weakened plane and acts as a dummy groove joint, can remain in place until the contractor is ready to seal the joint. Then it is removed with an abrasive blade slightly wider than the strip. Usually specifications require the removal of only the top 1 to 1½ inches of material.

One new development in equipment which is applicable only to highways is the traveling form paver. This machine operating on crawler tracks can

place a 24-foot wide slab up to 10 inches thick. Used to date on highway projects in several midwestern states, it permits rapid construction with a small paving crew to fairly accurate surface tolerances.

Another new pavement development of primary interest to maintenance engineers of highways and airports has been thin bonded concrete resurfacing. Using construction methods developed in the Portland Cement Association's laboratory and field tested on a number of jobs under severe conditions of exposure to weather and traffic, resurfacings of 1 inch or more can now be placed on old slabs suffering from scaling, popouts or other surface deterioration.




Photo courtesy Seaman-Andwall Corporation

A new development in connection with sawed joints is this special machine which vibrates a transverse metal bar into the concrete surface at the exact line of a proposed joint to displace the coarse aggregate. When the still-vibrating bar is removed, only mortar flows back into the groove. Use of this machine is said to result in important savings, since the joint can later be sawed with an ordinary abrasive blade in less time and at far less cost because the hard coarse aggregate has been displaced.

This method has been successfully used on the Pennsylvania Turnpike, two Air Force Bases and several bridges. It consists of removing all loose, unsound concrete from the surface with some type of cutting or chipping machine, removing oil and grease drippings with a detergent, etching the surface with muriatic acid, brushing into the surface a bonding coat of grout made up of a 1-1 sand-cement mix and finally placing the resurfacing concrete of the desired thickness using a mix of air-entrained concrete having about the same strength as the base slab, and coarse aggregate with a maximum size not over one-half the resurfacing thickness.

The large volume of stiff, low-slump concrete demanded by modern pavements brought about the use of internal vibration in slabs about 12 inches thick to insure proper consolidation.

Probably one of the more significant changes has been the increase in pavement thicknesses. Slabs of 19, 21 and even 24 inches are not uncommon at the heavy bomber bases being built today. This alone has tested the ingenuity of contractors and equipment manufacturers. Higher forms, heavier equipment and more mechanization are just a few of the apparent changes.

Higher forms and heavier equipment mean sturdier forms and more and longer form pins to hold them securely in place. Longer pins mean pneumatic tools for driving them and removing them. Hand tools are no longer adequate.

Thicker slabs mean larger volumes of concrete and more mixers or pavers

to make fast enough forward progress to permit proper timing of finishing and curing. More pavers in turn require larger batch plants capable of accurately proportioning and recording tremendous volumes of material. In a 10-hour construction day a typical batching plant may handle over 5 million, 800 thousand pounds of cement and aggregate to keep up with a paving crew using only two 34-E pavers, and many contractors will use more than this. Today's specifications call for each of the 1,110 batches in such a day to be automatically weighed and dumped and the precise weight of each ingredient in each batch electronically recorded on a continuous record.

Other fairly recent developments include polyethylene curing sheets,¹ Styrofoam joints,² the Chace pocket air indicator for measuring the air content of fresh concrete, the Willis-Hime test³ for measuring the cement content of plastic concrete, and soil-cement and cement treated base as subbases under concrete and bituminous surfaces. Probably the latest idea, still in the early experimental stages, is prestressed concrete pavements.⁴ All these developments bear out the observation that the whole field of concrete pavement construction is moving rapidly.

END

¹See "Polyethylene Film," *Concrete Construction*, January 1957, page 2.

²See "Rigid Plastic Foam," *Concrete Construction*, May 1957, page 8.

³See "A Quick Method for Determining Cement Content of Fresh Concrete," *Concrete Construction*, October 1957, page 8.

⁴See "Experimental Highway of Prestressed Concrete," *Concrete Construction*, July 1957, page 3.

One of the most recent developments in the field of concrete paving is an experimental prestressed concrete pavement. Here a paving machine at the right is placing concrete over the flexible conduits which contain the wire strands which were later post tensioned. The prestressing was done by leaving a 6-foot gap in the center of the strip and jacking the sections apart after the concrete had set. Advantages hoped for are the elimination of many transverse joints and the ability to provide for modern loads with thinner slabs.

Photo courtesy Jones & Laughlin Steel Corporation





Photo courtesy Dow Chemical Company

This picture shows rigid plastic foam being used to form transverse contraction joints. The joint groove is formed with a T-shaped metal bar immediately following the longitudinal float. When the metal bar is removed, the strip of plastic is inserted and the joint area is then finished by hand. This technique keeps the joint free of debris until the contractor gets around to installing a permanent joint sealer.



Ramp Garage Proves **Spanall** is Big Time-saver!

HORIZONTAL SHORING

Today there is no product, no method more efficient, nor more time-saving, than SPANALL—the modern, all-steel, horizontal shoring for all types of beam and slab concrete deck and floor forms.

This fact was well demonstrated in the construction of the Rochester (N. Y.) Municipal Parking Ramp Garage, as attested in the above letter from the general contractor. Plans called for a grid dome job, with clear spans of 14'0", 15'0" and 18'0"—the latter spans applying to the bays clearly indicated in the photo. SPANALL, spaced 2 feet o.c., were supported by 4 x 6 ledgers on 4 x 4 shores. Except for these 4 x 4 shores, the areas below the



SPANALL formwork remained free and clear for much needed traffic and uninterrupted work progress. Cost savings with SPANALL on this type of work average up to 40%.

That's why, on job after job, from coast to coast, in Canada and in Latin America, SPANALL is now accepted as *the* one time-saving, cost-saving horizontal shoring method for concrete floor and deck forms.

Call your local SPANALL distributor today for catalog and complete details. Or write directly to Dept. B.

Spanall of the Americas, Inc.
787 United Nations Plaza, New York 17, N. Y.



SPANALL—WITH BUILT-IN CAMBER—IS ENGINEERED FOR AMPLE LOAD-BEARING SAFETY FACTOR

If your bids on concrete construction work are based on hope rather than on knowledge of costs, here's a practical approach to bidding that can make the difference between profitable operations and possible bankruptcy.

Bids Should be Based on Knowledge

HARD, SHARP COMPETITION, such as characterizes the American business scene today, makes heavy demands on those who would play a vital role in this vast scheme of things. For those who are determined to survive beyond the short term, it places burdens that can be borne only by men who have mastered all of the factors involved in their particular field. For the man who wrests his living from the construction industry by competitive bidding, it is of vital importance to have a most complete and detailed knowledge of all costs that are involved in doing any one particular job. Yet the average small contractor has no time to make a detailed analysis of job costs, nor does he usually have the means to employ those who are competent to evaluate cost material and present it to

him in a usable form.

There is a way, however, to get on top of the cost study problem that is not financially burdensome, nor does it require neglecting other duties to spend time on the collection of cost data. Summer is the busy time and that is when a variety of jobs are available for study. It is also the time of year that many engineering students are available for summer jobs, and an engineering student that has finished this third year should be able to collect and evaluate detailed cost data on a number of jobs.

Some of this data can be collected from jobs being done by others. These cost items that are studied and recorded should include every detail of the work, in so far as is possible. It is of little value to sum up the cost of a

job, then bring the final result down to the average cost per cubic yard, and say that is what it costs to do work. Rather, set up in outline form each operation involved in setting forms, including transportation, storing, moving, erecting, oiling, maintenance, depreciation and similar items.

The list of items to be studied should be fully prepared before the study starts; winter is a good time to work up the outline to be followed. Then set your man to keep a close accounting of all the costs involved, including those that you may have omitted, in each of these operations. Do the same with placing, curing, patching and every other phase of your operations. When the work is finished the record should show in detail just where every nickel went. (MORE)

FORM A

Job _____ Date _____ By _____
At _____ Sheet _____ Of _____

Men On Job & Classification

- 1 Superintendent
- 1 Foreman (labor)
- 1 Timekeeper
- 1 Oper. Engr. (crane)
- 3 Oper. Engr. (rigs)
- 1 Oper. Engr. (F.E.L.)
- 1 Oiler
- 1 Master Mechanic
- 2 Chauffeur
- 12 Laborers

Equipment

- 1 Crane (38 B)
- 1 Front End Loader (1 yard)
- 3 Drill Rigs
- 2 Trucks (1 Repair Pickup,
1 Flat Bed)
- 1 Compressor (60 cu. ft., 1
Jackhammer)
- x Pumps

Description of Job Conditions

General description as to location, working room, accessibility, etc.
Soil condition as effecting digging, bottom and side condition, drainage, etc.
Disposal of excavated material
Accessibility to point of deposit for ready-mix concrete trucks
General description of operation

FORM B

Job **Memorial Hospital** Location **1000 B Street, City**
Architect **Black, White, & Associates** Made by **JAW** Date **12/15/56** Sheet **1** of **1**
For **General Contractors (6 requests)**
Owner takes bids at **150 E. State St., City** Jan. 17 57 2:00 PM CST
No. of Caissons **132** Base Length **65 ft.** Bells: with **120** without **12**
Diameters **2 ft. 6 in.; 3 ft. 6 in.; 4 ft. 0 in.** Base Volume **61,472 cubic feet**

A. Drilling Crew/Day

1 Superintendent.....	\$45.00
1 Foreman.....	28.27
1 Timekeeper.....	20.00
1 Master Mechanic.....	44.00*
1 Oper. Engr. (crane).....	42.30*
1 Oper. Engr. (F.E.L.).....	39.00*
5 Oper. Engr. (Rigs).....	190.20*
1 Oiler.....	26.50*
2 Chauffeur.....	58.20*
16 Laborers.....	440.00*
1 Iron Worker.....	42.60*

\$ 976.07

Payroll Expense @ 14%.....138.05

Total Labor Cost/Day.....1,114.12

B. Plant/Day

1 Crane.....	150.00
1 Front End Loader.....	50.00
5 Drill Rigs.....	300.00
1 Repair Truck.....	30.00
1 Flat Bed Truck.....	20.00
1 Pump - 2 inch.....	5.00
L.S. Small Tools & Supplies....	20.00

Total Plant/Day.....575.00

Schedule

Use 5 Rigs
Progress: 2 holes/shift/rig
Shafts/shift 10
Cubic feet/shift 4,660
Cost/cubic foot 0.3625

C. Material

Concrete, including waste	41,760.00
Casing.....	5,000.00
Disposal**.....	5,074.00
Fuel.....	1,166.00
Reinforcing.....	1,198.00
<u>Total Material Cost.....</u>	<u>54,198.00</u>

D. Indirect Cost

On
On & Off.....1,100.00
Travel & Expense.....200.00
Field Office.....500.00
Utilities.....750.00
Freight.....1,500.00

Total Indirect Cost 4,050.00

Labor-Plant Cost/Day Combined

Labor (item A).....	1,114.12
Plant (item B).....	575.00

Total Labor & Plant Cost/Day..1,689.12

Summary

Labor & Plant/cubic foot.....	0.37
Material/cubic foot.....	0.88
Indirect/cubic foot.....	0.07
Total Cost/cubic foot.....	1.32
Mark up.....	0.58
Bid/cubic foot.....	1.90

Lump Sum Bid 61,472 cubic feet @ \$1.90
per cubic foot

Total \$116,786.80

Extra for increased footage \$1.83/
cubic foot


Credit for decreased footage \$1.25/
cubic foot

*10 hour day
**Sub-contract

FORM C

Date _____ By _____

Job _____ At _____ Sheet _____ Of _____



Layout of Job and Movement of Rigs During Day

RIG	
A	Started 7:00; Belling 9:05; Finished 9:20. Moved by crane.
B	Started 7:00; Belling 9:30; Finished 9:45. Moved by own power.
C	Started 7:00; Finished 10:15. Moved by crane.
A	Started 9:29; Finished 1:20; Moved by crane.
B	Started 10:20; Belling 1:33; Finished 1:48. Moved by own power.
C	Started 10:34; Finished 3:50. Lost 2 hours, 20 minutes for repairs.

The two forms on these pages and the one on page 9 are designed to provide an orderly means of accumulating basic cost and operating information applicable to concrete construction work.

Why go to the trouble and expense of making such studies when you are now getting plenty of work and showing a profit? Besides, you say, you have been in the business for years and if there is one thing you know about the work it is what it costs. Here are a few suggested advantages that can accrue to you from such a cost study. The first advantage, and the one that is probably of greatest value, is the ability to take the results of the study, assemble them in whatever way is most convenient, and from them work up a cost estimating form that will include all of the costs that have been run down and evaluated. This form can be made to fit each individual organization's specific needs, and it can be

made to call attention to all of the costs normally involved. An open space is also recommended that will direct attention to the task of looking for extra or unusual costs.

The form should be so designed that it must be completely filled out before a cost figure can be determined. The use of this technique can ease and speed the work of estimating. A second advantage is elimination of unnecessary costs. You may find that you are doing work that could better be eliminated, or you may find that by changing a method you can make an overall saving. Third, you will have detailed, intimate, and up-to-date knowledge of the cost structure in your particular industry. And last, the student that you hired for the summer

may come back after graduation and develop into a very valuable employee. The construction industry can use more industry-trained engineers at all levels.

The suggested cost study will be both simplified and expedited by the adoption of simple forms for the systematic collection of the desired information. Of the forms accompanying this discussion, A and C provide for the accumulation of basic cost and operating information for the job-cost study to be made, while Form B is simply an estimating sheet specifically adapted to concrete construction work. A good take-off man working with forms of this type can save a busy contractor a lot of time, money and aspirin.

END

Low temperatures bring out the best in COLUMBIA CALCIUM CHLORIDE


This means ready mix now sets faster

Finishers move in and off ahead of schedule, saving costly overtime. That's because Columbia Calcium Chloride used in ready mix produces both initial and final sets a full *three times faster!* And does it while exceeding the most rigid strength specs. Your customers pull forms days earlier, move on to the next job. Giving them the built-in protection of this chemical that just warms up to cold winter weather is pretty good insurance that their ready mix orders will keep coming to you. And Columbia Calcium Chloride provides no handling problem for you at all . . . adds equally well at your plant or customers' job sites.




Faster early strength (50% greater at 72 hours) lets most skilled trades get to work without delay and resulting overtime.

And concrete products set faster, too



Units move faster and store better when Columbia Calcium Chloride is part of the mix. Pre-cast block, panel, or pipe products cure days faster with substantially reduced breakage and chipping. Columbia Calcium Chloride has the unique property of working hardest when the temperature drops to 50° or below. You can safely cut pre-steam holding time, steaming and soaking periods. You'll experience far less cracking during early handling, too. With faster production, you save on inventory, as well. Customers get better concrete products, with deliveries dovetailed more dependably to their construction timetables. It's a great way to build business.

Columbia Calcium Chloride works uniformly well in concrete made from normal, air entrained and high early cements.



WRITE TODAY FOR MORE INFORMATION...PLEASE SAY WHETHER INTERESTED IN READY MIX OR CONCRETE PRODUCTS

COLUMBIA-SOUTHERN CHEMICAL CORPORATION

SUBSIDIARY OF PITTSBURGH PLATE GLASS COMPANY
ONE GATEWAY CENTER • PITTSBURGH 22 • PENNSYLVANIA



DISTRICT OFFICES: Cincinnati • Charlotte • Chicago
Cleveland • Boston • New York • St. Louis • Minneapolis
New Orleans • Dallas • Houston • Pittsburgh • Philadelphia
San Francisco

IN CANADA: Standard Chemical Limited and its Commercial
Chemicals Division



A close-up view of the dimpled concrete. While the plastic film gives the concrete a glossy surface, shadows and highlights are provided by the dimples which are formed by the underlying layer of crushed rock.

Another article in our series on special finishes for concrete. Although the technique described may seem highly specialized, it has interesting possibilities.

Dimpled Concrete

By E. L. Howard and Don McDonald

Pacific Cement & Aggregates, Inc.
San Francisco, California

YOU GET ACCUSTOMED to some unusual specifications in the concrete game, but we were admittedly stumped for a while when one of the requirements of a recent job was that the concrete surface be rough enough so that youngsters would be unable to write on it. This strange requirement turned up in connection with a tilt-up wall project, in which great stress was also laid on the need that the wall be attractive, inexpensive and easy to apply.

Our first attempt was to pour concrete on a rubber mat having waffle-like indentations. Developed in Great Britain, this process was first described in the September 1956 issue of *CONCRETE CONSTRUCTION*, page 10, and a follow-up article also appeared on page 13 of the July 1957 issue. The process consists of lining formwork with rubber sheeting of any desired pattern and texture, placing and vibrating the concrete against the sheeting to cast its pattern into the surface of the structure, and finally stripping

the rubber sheeting away from the concrete surface. Normally the sheeting is either glued to the forms or fastened by means of clips, but in the experimental work we conducted for tilt-up wall construction the sheeting was simply laid on the casting surface. We found that suitable rubber matting could be obtained in many patterns, and laid in strips or squares to achieve any effect the designer might wish. Unfortunately the cost proved to be prohibitive on our particular project, and we were compelled to look elsewhere for a solution.

We therefore conducted experiments in our laboratory with a view to developing some technique which would result in a very rough concrete surface at low cost. Small casting panels were built and filled with several sizes of gravel and crushed rock, and then covered with plastic membrane to form the base material for casting concrete. Under laboratory conditions it was found that the underside of the slab

could be roughened in this fashion in many attractive patterns by simply varying the base material.

When a satisfactory amount of experience had been gained in the laboratory, the technique was then tested under actual job conditions. It was found that standard procedures used in tilt-up construction could be adhered to with entirely satisfactory results. Although it was found that particular care should be used in spreading the base rock and overlaying it with the plastic sheet, there was nothing about this work that could not be performed by the ordinary contractor's crew. It developed that the plastic material formed dimples more readily on warm, sunny days, but it proved to be a simple matter on cold days to warm the sheets before applying them.

It is our belief that the dimpled surfaces produced by the use of a base rock course and plastic sheeting have a place in home and industrial concrete as well as in schools. We know of at least one contractor who plans to precast sidewalk and patio sections by this method. The limited work we have done indicates that the use of several sizes of base rock would provide a ready means of varying the dimple pattern. By this means, and with a very little practice, it seems certain that many attractive surfaces could be produced.

The process can also be varied to produce an attractive exposed aggregate surface. In place of the plastic sheets, this would involve using a colored stone base material covered with mortar worked well into the voids. The mortar should be fresh when the concrete is poured and deep enough to allow bonding with the poured concrete. The colors of the exposed rock can be highlighted by using a white cement-sand mortar, and some designs may include the use of redwood strips and other such devices to achieve special effects.

Actually, the only real limitation on the possible decorative patterns which may be achieved in this fashion is the limitation on the imagination itself. With more and more emphasis being laid these days on the elimination of special finishing operations after concrete has been placed, it is our belief that designers and field men will eagerly explore the possibilities of a technique that so readily and cheaply makes it possible to cast attractive surfaces right into the concrete. END




One of the dimpled concrete wall panels after it had been stripped from the form and tilted into place. Conventional tilt-up procedures were used throughout the casting of these panels, with the exception of the use of a crushed rock base course and plastic film producing the dimpled surface.

Here workmen are carefully anchoring the plastic film material to the side forms. Note that the crushed aggregate base material is already in place inside the form.



No time lost when concrete is



SPECIAL WINTERIZED

with SOLVAY CALCIUM CHLORIDE

You save four ways when you order ready-mix that is "special winterized," including SOLVAY Calcium Chloride:

1. You save overtime finishing, because it sets faster.
2. You save delays in form removal, because it develops high early strength.
3. You save delays between operations.
4. You can save up to 50% on protection time.

**SOLVAY CALCIUM CHLORIDE SPEEDS BUT DOES NOT
CHANGE THE NORMAL CHEMICAL ACTION OF
PORTLAND CEMENT**

Impartial tests by the National Bureau of Standards prove its advantages in cold weather construction and concrete work. It is recommended or approved by leading authorities, including American Concrete Institute and Portland Cement Association.

For the low cost of adding 2% of SOLVAY Calcium Chloride to concrete, you can actually maintain warm weather working schedules in winter. And you get *better* concrete! Ultimate strength at one to three years is actually 8 to 12% greater. Your product is more workable.

With less water-cement ratio, you get denser, more moisture-and-wear-resistant concrete.



**Handy
25 lb. bag**

**Easy to use
Assures accurate
measure**

Write now for full data!



SOLVAY PROCESS DIVISION

ALLIED CHEMICAL & DYE CORPORATION
61 Broadway, New York 6, N. Y.

Please send without obligation your booklet:

- ☐ "When the temperature drops BELOW 50°F., do you know what happens to CONCRETE?"
- ☐ "The Effects of Calcium Chloride on Portland Cement."

NAME _____

POSITION _____

COMPANY _____ PHONE _____

ADDRESS _____

CITY _____ ZONE _____ STATE _____ 83-28



SYMONS FORMS keep jobs moving on a time saving schedule




There are four principal reasons for the high acceptance of Symons Forms in the home and light construction market.

1. They can be quickly and easily set-up and stripped
2. Wood-Ply Forms have often lasted for more than 200 uses . . . frames of Mag-Ply Forms will last indefinitely
3. Forms can be used on any type of general construction . . . they are not confined to a single type of application
4. Symons engineers and field representatives can help you with any forming problem

← "CHAMP"—Inexpensive Wood-Ply Form

Here is an efficient and accurate form at a cost approximately 20% less than Symons Standard Panel Form. Designed primarily for light commercial and residential construction, it is equally satisfactory for high pours where strength and durability are "musts."



"MAG-PLY"—Hi-First Cost, Lo-Per-Use Cost →

Initial cost of this lightweight form is high. However, the many reuses possible makes the cost per use exceedingly low. Form averages only 3 pounds per square foot. Frame of extruded, rust-proof magnesium completely encases the plywood face. $2\frac{1}{2}$ " wide frame reduces loading and storage space.

Symons Forms can be rented with purchase option
Complete details on Symons Forms available upon request

 **Symons CLAMP AND MFG. CO.**

4271 Diversey Avenue • Dept. B8 • Chicago 39, Illinois


Many contractors prefer large panels for concrete forming

Symons develops long life, labor saving Wide Panel Forms

Many concrete contractors that have been in the business for years prefer the large 4' x 6' and 4' x 8' panels. They believe these panels are the cheapest and the best for house foundations. The wide panels can be used horizontally for crawl space foundations or vertically for basements.

Large panels often weigh at least 100 lbs. when dry and far more when wet. It is not always easy to find men willing to carry these wide panels single-handed. There are, however, crews that will and the men take much pride in being able to carry the heavy weight panels.

Three Types of Large Panels



"H" Form

For contractors that prefer wide panel forms, Symons Clamp & Mfg. Co. has devel-

oped three types of large panels. Two of these have wood frames reinforced



Wide Panel with Steel Struts



Wide Mag-Ply

with steel. The advantage of the wood rimmed forms is their low first cost and their adaptability for all kinds of jobs. The third type has a magnesium frame that protects the plywood edges and provides ample strength with light weight. Magnesium Forms are expensive, but will give a very low cost per use to the contractor who can use them fifty or more times per year.

Only 3 Basic Pieces of Hardware

Symons forming system includes just 3 pieces . . . form tie, connecting bolt and wedge. Connecting bolt is inserted through adjoining forms and the loop of the tie. Wedge is inserted through the connecting bolt, locking and joining the panels. Its use with your present forms will make possible considerable savings in labor.

Form Engineering Available

Our sales engineers will be glad to discuss your forming problems and will make estimates, layouts and recommendations for the most efficient and cost saving method of forming, without charge or obligation. Write, Symons Clamp & Mfg. Co., 4271 Diversey Avenue, Dept. B-8, Chicago 39, Illinois. Your inquiry will be forwarded to the local Symons representative.

CONCRETE CONSTRUCTION

from the makers of . . .

Protex



PDA

FIELD PROVEN ECONOMY
in all phases of Concrete Placement!

PROTEX Dispersing Agent . .



PDA increases strength at any age through water reduction and cement dispersion, improving all the desirable characteristics of concrete, giving a "live" concrete with protection against "hot weather" slump loss and segregation—allows the placing of controlled durable air entrained concrete without plastic shrinkage cracks. PDA is a selective initial retarder—retarding only the initial set of concrete for extended vibration and finishing time (not delaying form stripping time) YET it gives no retardation in winter concreting—thus year around benefits are obtained with "all season" PDA.

PDA . . . packaged in a durable bag . . . comes to you in convenient powder form . . . easily mixed and dispensed . . . complete dispensing installations available upon request.



This is the Breed Plant of the Indiana-Michigan Electric Company at Sullivan, Indiana, where over 55,000 cubic yards of concrete with PDA are being successfully placed.

Proven, Dependable, Adaptable

Proven in the field . . . PDA insures the successful and economical placement of better quality concrete!

Dependable — YES! Proof positive from Government and private projects. Also backed by the world-known and world-respected PROTEX name!

Adaptable to any need . . . PDA improves any Pre-stressed, Slip-form, Light-weight, Tunnel-lining, Tilt-up or Lift-slab concrete project!

PDA's basic material is purified and desugared having been field tested and proven over past years giving you all the well known benefits — greatest water reduction — cement dispersion — maximum workability and durability — plus PROTEX economy and reliability.

FOR BETTER AND MORE ECONOMICAL PLACEMENT OF CONCRETE, SPECIFY AND USE PDA...FROM THE MAKERS OF PROTEX!

Please send now, informative FREE booklet "PDA - Protex Dispersing Agent"

Firm Name _____

Attention of: _____

Address _____

City _____

State _____

* T.M. Reg.



AUTOLENE LUBRICANTS COMPANY

Industrial & Research Division

1331 WEST EVANS AVENUE

DENVER 9, COLORADO




Photo courtesy Slow Manufacturing Co.

A bucket and crane was used to place the dry mix to the height of the forms on the Bradford flood wall project.

How to Place Concrete on a Slope

WHILE IT IS NOT AT ALL uncommon to encounter jobs that require both vibrating and screeding concrete on a slope, it is quite unusual to find these two operations being performed simultaneously with the same piece of equipment. This feat has been accomplished with good success and economy on an 8-inch thick concrete flood wall slab recently constructed at Bradford, Pennsylvania.

It was necessary to lay the slab on a bank that had a $1\frac{1}{2}:1$ slope, and a further requirement of the specifications was the use of a $1\frac{1}{2}$ -inch slump concrete with gravel ranging in size from $1\frac{1}{2}$ inch to 2 inches.

The successful bidder on this project was the Elmhurst Contracting Company of New York City, and the problem of vibrating the concrete on the steep slope was successfully solved through the use of a vibrating screed measuring 15 feet in length. Two gasoline-powered vibrating packs were used on the screed, and special mounting brackets were provided so that the

engines could be placed in a vertical position while the beam remained perpendicular to the side slope.

Probably the most serious problem encountered concerned the maneuvering of the vibrating screed. Although it would have been preferable to do the screeding from the top of the slope to the bottom in order to take advantage of gravity, it was found that this procedure caused the concrete to flow too rapidly ahead of the beam. Although this difficulty was promptly solved by screeding from the bottom to the top, it proved to be back-breaking work to move the screed against its own weight and the drag of the concrete. This was solved by using the power winch on a tow truck and simply hooking the cable to the screed and pulling it up the slope.

As the accompanying pictures show, the concrete was placed by bucket to the approximate height of the forms. When an entire 15-foot wide by 18-foot high section had been covered with the stiff mix, the screed engines

were started up at the bottom of the slab. The screed was then slowly pulled up the face of the concrete by means of the winch cable which was attached to an eyebolt in the center of the screed beam. The tow truck was normally operated on the top of the bank, but when there was insufficient room for this a sheave was provided at the top to permit the truck to operate below the bank. Moving on rollers which engaged the side forms, the vibrating screed moved slowly up the embankment, both striking off and consolidating the concrete as it passed.

It was found that under favorable conditions only one pass was required to obtain a satisfactory finish. Although on rare occasions the appearance of concrete bulges behind the screed made it necessary to make a second pass, even with these delays it was found that the average time for striking off and vibrating each section of the concrete was only a little over a minute. Upon the completion of each pass, the vibrating screed was attached by the




Here the vibrating screed is starting its pass from the bottom of the slope to the top. Note the cable attached at the center to ease the work of moving the heavy beam up the steep slope. The vibrating power units are driven by 2½ hp. gasoline engines.

Here the screed has finished its pass and is ready to be moved to the bottom of an adjoining section. Final finishing is done by means of hand trowels.

eyebolt to the cable on a crane and lifted to the bottom of the adjoining section of floodwall. The final finish of the slab was obtained by means of hand trowelling.

It is the contractor's belief that the savings obtained by simultaneous vibrating and screeding might possibly run as high as 20 percent. It was found possible to place and finish approximately 44 cubic yards of concrete each day in this fashion—enough to complete eight of the 15 by 18-foot sections. The 3-mile floodwall was constructed for the Corps of Engineers under a 2.2 million dollar contract.

The normal procedure on a job of this type would have been to vibrate the concrete first with internal vibrators, and afterward to do the screeding as a separate operation. It is believed that the successful use of a vibrating screed on the Bradford flood wall was mainly the result of two favorable circumstances: The comparatively thin slab and the fact that the reinforcing steel was widely spaced. **END**



Chicago is scene of first annual convention of National Concrete Contractors Association

Readers of Concrete Construction who plan to attend the first annual NCCA convention will find the complete program of this important meeting in the adjoining column. Opening in Chicago on Monday, February 24, with registration of members at the Morrison Hotel and the Coliseum, this convention will bring concrete contractors from all over the country together for the first time in history.

The Chicago convention carries out a decision reached by an organizing committee which met in the same city last summer to draft a preliminary constitution and set of by-laws. Among the objectives outlined for the new association at that time was the establishment of uniform standards within the industry, the promotion of better business relationships between concrete contractors and their suppliers, and the dissemination of accurate information concerning products and methods.

Under the direction of Jim St. Clair, chairman protem of the convention and executive secretary of the Concrete Contractors Association of Greater Chicago, the first session of the meeting will square off to the important job of forming working committees and selecting a slate of officers and directors to be elected on February 26, the final day of the convention. Committees and their chairmen will be selected from the association membership by the already-established executive policy committee.

A major highlight of the convention program will be an address by Roger H. Corbetta, president of the well-known construction firm which bears his name, and also a director of the Concrete Industry Board of New York City. Mr. Corbetta was one of the founders of the Concrete Industry Board, an organization which has been outstandingly successful in serving as a watchdog in matters affecting the quality and performance of concrete construction work. He is a vigorous and able speaker, as well as one of the most widely experienced and best informed concrete construction men in the country.

An important feature of the Chicago convention will be an exposition of products and processes related to concrete construction work. This trade show of the industry will be housed in Chicago's venerable Coliseum, where the convention sessions will also be held.

Also being offered to members in connection with their attendance at the convention is a tour of the Marquette Cement Manufacturing Company's new plant in nearby Milwaukee on Thursday, February 27. Members of NCCA are invited to attend the technical sessions of the American Concrete Institute which will be held in Chicago's Morrison Hotel on the same dates as the concrete contractors' meeting. ACI members are also invited to attend the NCCA sessions.

On the social side, the convention program includes a banquet to be held at the Morrison Hotel at 8:00 P. M. on

February 26. The ladies' program will include a fashion show to be held at the Terrace Casino of the Morrison Hotel and a conducted tour of Marshall Field's department store.

CONVENTION PROGRAM

February 24, 25 and 26, 1958

CHICAGO COLISEUM

ALL CONVENTION SESSIONS TO BE HELD IN
THE CHICAGO COLISEUM

Pre-Convention executive session
Sunday, February 23

Registration: Monday, February 24

Morrison Hotel—Beginning at 8:00 AM

Chicago Coliseum—Beginning at 8:45 AM

Monday—February 24

Convention sessions 9:00 AM to 12:00 Noon
Opening Session

Invocation

Preview Program for Convention—Jim St. Clair

Name working committees, chairmen and
meeting sites

Break

Speaker—Roger H. Corbetta, President
Corbetta Construction Co., Inc.—New
York, N. Y.

Adjourn 12:00 Noon

Trade Show opens at Noon today and runs to
6:00 PM

Tuesday—February 25

Convention session opens 9:00 AM

Committee Reports

Adjourn 12:00 Noon

Trade Show—12:00 Noon to 9:00 PM

Wednesday—February 26

Trade Show—9:00 AM to 5:00 PM

Convention Session opens 1:00 PM

Conclusion of unfinished business

Election of Officers and Directors

Adjourn at termination of business

Convention Banquet—8:00 PM

Morrison Hotel

Thursday—February 27

Tour of Marquette Cement Plant in Milwaukee

Friday—February 28

Departure for Hawaii from Midway Airport
—12:00 Midnight

LADIES' PROGRAM—The Chicago Hostess Committee has planned an enjoyable program of sight-seeing and entertainment.

**Wherever Better
Homes Are Built ...**

You'll Always Find

**NEW MONARCH
IN-A-SLIDE**

Basement Windows

More and more discriminating home owners are telling their builder that New Monarch IN-A-SLIDE basement windows are a must for their new homes. And more and more builders themselves are suggesting IN-A-SLIDES.



Homeowners who install In-A-Slides get:

1. Double weather protection against rain, snow, dust.
2. Better light and ventilation with a window that opens to a 60 degree angle.
3. Easy removability of sash for easy glazing and inter-changing.
4. Screens and storm sash to match.
5. Phosphate coating after fabrication, giving protection against rust.
6. A sturdy strong steel window, press-formed from heavy gauge steel with reinforced, spot welded-corners.

And the builder gets

1. The window that is so perfectly balanced, so easy to install that it stands alone.
2. A window that will bring him more satisfied home-owners . . . more customers.
3. A window that is easy to handle . . . sturdy enough to withstand the roughest handling.
4. A window that's trouble-free and eliminates service calls.

*To Hear The Full IN-A-SLIDE Story, Write Today To:
R. S. ... 194 At The Convention*


Order early for your high profit best seller ...
For further information, Write Today to

NEW MONARCH

MAXIMUM AND PLANNING CO.
404 S. W. NINTH STREET, DES MOINES 6, IOWA

**Make Big Profits
From IN-A-SLIDES
For Other Uses Too**

- FOR FARM BUILDINGS
- FOR GARAGES
- FOR COMMERCIAL BUILDINGS



**NOW -
NO
MORE
BUCKS!**

The new In-A-Instant adapter fits the Monarch In-A-Slide window and is permanently attached to the pouring forms thus eliminating heavy bucks in poured concrete foundations.

Time, trouble, and labor costs are saved because the new In-A-Instant adapter is wall thick for 8", 9", and 10" walls, requires no stripping, is easy to assemble and install by one man, and is shipped flat for low cost storage.

The In-A-Instant Adaption makes the In-A-Slide Window even more attractive to the Builder Who Pours Foundations!

Shoring Methods . . .



by Patent Scaffolding Co.

SAME COMPONENTS PROVIDE SHORING AND PLATFORMS; SPEED HUGE PARABOLIC ARCH

FOR BUILDING this huge, spine-like, 240'-long parabolic arch for the new, modern-design Yale University Hockey Rink, contractor, George B.H. Macomber Co., makes effective use of "Trouble Saver"® Scaffolding components for shoring and for working platforms.


2'-wide "Trouble Saver" Shoring units with built-in ladders support the area starting 21' in from each end of the arch. For a distance of 32' these units are placed 5' apart, perpendicular to the arch length, with 6" spacing between towers. The next 59' is shored with 5'-wide "Trouble Saver" frames, spaced 37" apart, parallel with the arch length, with 8" spacing between towers. 475 5'-wide frames and 410 2'-wide frames are in use. Horizontal bracing is achieved by "TubeLox"® Scaffolding members and 56 steel cable guys.

A separate working platform, made of 285 5'-wide "Trouble Saver" frames, is used on one side of the arch only for easy placing and removal of forms. "TubeLox" Scaffolding members tie this working platform to the shoring for extra safety.



HIGH, HEAVY BEAM SUPPORT—Southern Bldrs., Inc., needs only 228 "Trouble Saver" Shoring ladder frames, braced with "TubeLox" Scaffolding members, to support this 50'-high, 8'-thick arched concrete beam for St. Marks Church, Shreveport, La. Built-in ladders provide quick access for workers.

To help you with your scaffolding and concrete shoring methods, PS offers a complete nation-wide engineering service available to you locally. See the Yellow Pages in your 'phone directory for the nearest Patent Scaffolding office or representative that sells and rents "Gold Medal" Scaffolds.



QUICK, STRONG BRIDGE SHORING—Due to its high load-bearing capacity, "Trouble Saver" Steel Shoring permits Snitely Brothers, contractor, to get an entirely accurate camber section for this 2-arch (each 52' long) underpass bridge on the new Peninsula Drive near Moses Lake, Wash. 396 shoring frames of various heights are erected quickly to support the slab thickness of 2'4" at pier edges and 1'2" at the 18'-high midspan points. By using versatile, prefabricated steel shoring, instead of wood, forming costs for highway bridges, overpasses and piers can be cut at least 25%. Highway Bulletin G208 gives complete facts, ask for it.

FOR GREATER SAFETY...EFFICIENCY...ECONOMY



THE PATENT SCAFFOLDING CO., Inc.

38-21 12th Street Dept. 000, Long Island City 1, N. Y.
West Coast: 6931 Stanford Ave., Los Angeles 1, Calif.
In Canada: 355 Dufferin St., Toronto
Branches in all principal cities

questions

QUESTION: Has any study been made to determine the best time of the year to apply paint to concrete slabs to mark traffic and parking lanes?

ANSWER: A study by the New Jersey Zinc Company was reported in the October, 1943, issue of *Paint Progress* magazine. The conclusion reached in this article is that the best time to apply traffic paint is at the beginning of a dry season, since durability seems to be harmed by excessive moisture during early months of exposure.

QUESTION: Have any articles been published on the pros and cons of leasing or owning automobiles and trucks?

ANSWER: Two articles on this subject have been published in the *Harvard Business Review*. One appeared in the March-April 1955 issue on page 75 entitled "Pros and Cons of Leasing Equipment" by Frank K. Greisinger. The other appeared in the July-August 1954 issue on page 108 under the title "Trend to Fleet Leasing" by John W. Rollins.

QUESTION: Is the hammer test reliable for determining whether or not concrete has been frozen?

ANSWER: Unfortunately frozen concrete may give the same ring when struck with a hammer as properly hardened concrete. A more reliable test is to apply hot water to the surface. If the concrete is frozen the surface material will soften.


QUESTION: How soon should concrete be placed in the forms after it is mixed?

ANSWER: There is actually a great deal more latitude than is generally supposed, but the common practice is to try to have the concrete in place within 45 minutes after mixing.

QUESTION: Does the presence of entrained air in concrete have an adverse effect on its abrasion resistance?

ANSWER: The effect should be negligible if the air content is kept below 6 percent, and proper curing conditions are provided.

Powerful small diameter vibrators for prestressed concrete




TO SOLVE the problem of consolidating low slump concrete in narrow, constricted areas, Viber offers these powerful, small diameter vibrators.

In addition to outstanding performance, they combine lightweight and compact design, making them remarkably easy for operation by one man.

Model 11A, weighing only 17 pounds, is amazingly effective for a unit of such small diameter. It is ideal for slip-form work and indispensable for use in constricted areas where standard vibrators are impractical.

Model 26, a full-powered small diameter vibrator is available with extended lengths of flexible drive. Head is interchangeable with Model 11A. It is especially popular in prestress manufacture because the small diameter head operates with great effectiveness in constricted, hard-to-reach places. Equipped with 4 feet of drive it weighs 37 pounds.

Tip of vibrator housing is replaceable. Viber's patented rubber tip furnished unless steel specified.



Contact your nearest dealer or write direct for further information and prices.

VIBER COMPANY, 726 South Flower Street,
Burbank 74, California



VIBRATORS

Pioneers and leaders in the manufacture of vibrators.


equipment

tools

materials

Additional free information concerning any item described in these columns may be obtained by filling

out and mailing the postage-free reader service cards which may be found in the center spread of this issue.



This amazing new tool works like MAGIC ANYWHERE you have a pier, wall or beam of any dimension to form up for concrete pour. Simple and practical.



The JIFFY is positively the latest form accessory on the market and is guaranteed to at least HALF your cost.

Bracket Clamp

Cost savings of as much as 50 per cent are claimed in the forming of columns, corner piers and deep concrete beams with a new accessory bracket clamp pictured here. According to the manufacturer considerable economy can be achieved because a relatively small number of the clamps suffices for almost any job without sacrificing either quality or safety. These adjustable clamps can be purchased or rented. **Jiffy Clamp Company, 2130 Wiley Street, Hollywood, California.**

Steel Paving Form

Wedge-Lok makes a rigid joint between forms for road building. Sections are joined to form a continuous beam, eliminating joint deflection. The forms are made from heavy duty 1/4-inch steel plate. Stake pockets, guides and Wedge-Lok are welded; there are no rivets to loosen. Base of forms is beveled at end for inside curves. Stakes are 1-inch diameter heavy duty high carbon steel. **Clark Industries, Paving Form Division, 375 East Fifth Avenue, Columbus, Ohio.**



Bantam Tractor

This midget tractor now offers a hydraulic dump as optional equipment. The bucket can be held rigidly at any desired angle with the ground, and rotated while in motion to dig and scoop up the largest possible load. By rolling the bucket lip up, larger loads can be carried, heaped above the rim of the bucket and even wet or liquid material can be retained. **Mead Specialties Company, Dept. SC-39, 4114 North Knox Avenue, Chicago 41, Illinois.**

External Vibrator

Pictured here in use on concrete formwork is a low-maintenance pneumatic vibrator designed for external use only. It has only one moving part—an air jet driven rotary eccentric turbine of bronze alloy. Up to 8 thousand 2600-pound blows are struck per minute on the largest forms. Steam and hydraulic driven models are also available for special application. **McCarron Brothers, P. O. Box 336, Baldwin Park, California.**



equipment and tools

For additional free information
mail cards facing page 16.


Form Sprayer

A lightweight, high-volume spray rig pumps liquid water repellents, form oils and similar fluids direct from original 55-gallon drums to spray nozzle. Fingertip trigger on spray gun automatically starts and stops the lightweight air-powered pump. Adjustable nozzle on gun can be quickly varied for heavy or fine spray to suit the operation. **Gray Company, Inc., 1002 Sibley Street N.E., Minneapolis 13, Minnesota.**



Concrete Bucket

Fully automatic, this 13-cubic foot concrete bucket is designed as companion accessory for Tusk Hoist. Bucket, which is interchangeable with platform, may be operated from the ground or from any working height up to 100 feet. Movement up and down is automatically controlled. **Tusk Division, Tubular Structures Corporation, 2960 Marsh Street, Los Angeles 39, California.**



Raising the level of construction standards...



VALPARAISO UNIVERSITY CHAPEL
Hagerman Construction Co., Gen. Contr.

...At Lower Cost!

Construction men undertake bigger and more complex jobs every day — still, they manage to complete them in record time when the proper equipment and engineering know-how are employed. Such was the case in construction of Valparaiso University Chapel. The project demanded scaffolding sturdy enough to support heavy concrete beams, yet sufficiently flexible to conform to the irregular contour of masonry walls. ADVANCE tubular steel Scaffold and components were more than equal to the task . . . fulfilling all job requirements for faster, safer and more economical workmanship.

Yes, ADVANCE applications of all types are doing much to raise the performance standards of the entire construction industry. That's why building and trade contractors, everywhere, are availing themselves of BEAVER-ADVANCE free Engineering and Field Service. It assures them utmost product efficiency and profits on every building project. Want proof? Call us in on your next job!



Beaver-Advance

CORPORATION
Ellwood City, Pennsylvania

Send for this descriptive catalog, it's FREE!

BEAVER-ADVANCE CORPORATION., ELLWOOD CITY, PA.


Name.....
Company.....
Address.....
City..... Zone..... State.....



equipment tools materials

Additional free information concerning any item described in these columns may be obtained by filling

out and mailing the postage-free reader service cards which may be found in the center spread of this issue.





Construction Jack

A new type jack features removable end linkages achieved by bolt joint, providing greater flexibility of use. Various type linkage methods can be interchanged to provide a wide range of applications or it can be used without linkage, permitting special hook-ups through screw eyes for special jobs. Designed for work on coffer dams, concrete and steel construction requiring false work or framing, bridge construction and maintenance, marine towing and wharf activities, the jack can be furnished with any combination of hooks including shackles. **Templeton, Kenly and Company, Broadview, Illinois.**

Truck Crane

This new, air controlled truck crane is a heavy duty machine with a rated capacity of 40 tons which can be easily and quickly stripped for travel. To accomplish this the truck crane is equipped with a new outrigger system which permits substantial weight reductions in the carrier while providing a solid, steady foundation for the powerful, massive crane upper works and deep section boom needed for a crane of this capacity. The carrier is available in 9- and 10-foot widths and the comfortable cab provides good visibility. **American Hoist & Derrick Company, 63 South Robert, St. Paul, Minnesota.**



Joint Groover

This joint groover widens or cleans sawed or hand formed joints in cement or bituminous concrete, new or old, widens sawed joints in new concrete before sealing, removes old seal material for resealing maintenance jobs, mills and widens, without spalling, random or uncontrolled cracks in cement or bituminous concrete, to width and depth for proper sealing. Bit will enter a crack 1/32-inch wide, or will make a groove where no crack exists. **Windsor Machinery Corporation, 85 Grassmere Avenue, Elmwood 10, Connecticut.**

Concrete Cleaner

A new acid in powder form is mixed with water, applied in the same manner as muriatic acid and when surface is clean, flushed away with water. Unlike muriatic acid it does not fume, is less corrosive to metals and will not discolor white cements. The product is recommended for use prior to applying paint to concrete surfaces to assure beautiful, long-lasting paint jobs. It is safe and effective whether used by professional workers or amateurs. **The Garman Company, Inc., St. Louis 23, Missouri.**




equipment and tools

For more information mail cards facing page 16.

Column Form Design Calculator

Construction costs are reduced by using standardized column form designs that are easy to erect and fast to strip. A pocket calculator answers troublesome problems of form design on columns and piers up to 48 inches square or 65 inches diameter, including rectangular cross sections. It specifies the correct lumber sizes, the arrangement and spacing of the bracing members, and the proper size and spacing of the steel strapping which replaces clamps in these designs. **Signode Steel Strapping Company, Calculator Department, 2600 North Western Avenue, Chicago 47, Illinois.**



Power Buggy

Carrying 3000 pounds in an 18-cubic foot hopper, the Moto-Bug climbs a 25 percent grade and turns in an 82-inch radius. As a forklift it raises 1500 pounds to 7 feet turning in an 84-inch radius. Direct drive to the power flow transmission allows a 12-mph. forward or reverse speed. The engine is sidemounted for operator comfort. Rear-wheel steering and internal expanding brakes are automotive type. Electric starting and L. P. gas equipment are optional. **Kwik-Mix Company, Division of Koehring Company, Port Washington, Wisconsin.**



FEBRUARY 1958

Simplex FOOT-A-MINUTE forms

OFFER YOU ADVANTAGES
THAT MEAN MORE PROFIT



**FASTER SET-UP and STRIPPING
NO LOOSE HARDWARE**

1 PATENTED LOCKING LEVER



Made of precision-finished, hardened steel. Bolted permanently to forms. A tap on lever locks or unlocks it. Cam action pulls panels together, minimizing seam marks, and giving positive wall dimension.

2 SIMPLEX TIE WIRES



Specially designed steel tie wires are made to withstand pressures up to 4,000 lbs., yet easily broken off without twisting in wall. Simple to drop in place... held securely by locking lever.

3 PLASTIC PANELS

Simplex panels are highest grade 1 1/4" impregnated plastic plywood backed with four 2" x 1/4" metal bars running the full width of each 8' panel. Construction gives greater strength than 2 x 4 backed forms with double walers. Full size 2' x 8' panel weighs only 65 lbs. Four, six and ten foot panels also available.


**IT ALL ADDS UP TO A COMPLETE
FOUNDATION IN 24-MAN HOURS
OR LESS WITH REDUCED LABOR COSTS**

Simplex FOOT-A-MINUTE forms

SIMPLEX FORMS SYSTEM, INC.
5603 INDUSTRIAL AVE., ROCKFORD, ILL.

WEATHER OR NOT... SIKACRETE GIVES YOU

- **EARLY FLOOR FINISHING**
- **EARLY STRENGTH**



Sikacrete Accelerating Densifier causes early set and quick strength development in both concrete and mortar — thus saving many costly hours of overtime finishing.

Sikacrete is a liquid admixture which enables you to place high quality concrete floors — despite cold weather.

Moreover, Sikacrete gives you these big advantages: greater density, hard non-dusting surfaces, increased ultimate strength and reduced cracking. For complete information, write for Bulletin SI-57.

26-3



PASSAIC, NEW JERSEY

DISTRICT OFFICES: BOSTON • CHICAGO
DALLAS • DETROIT • PHILADELPHIA
PITTSBURGH • SALT LAKE CITY • WASHINGTON,
D.C. • DEALERS IN PRINCIPAL CITIES
AFFILIATES AROUND THE WORLD

equipment tools and materials

Additional free information concerning these items may be obtained by mailing the reader service cards in the center spread of this issue.





Hoist Platform Cage

This cage, for use where loads must be hoisted on a closed platform, is built to fit the standard Buck platform. It does not have to be removed when the Hoistower is raised or lowered. The Buck Portable Hoistower can be transported with the cage installed. An automatic gate is available. **Buck Equipment Corporation, 720-X Anderson Ferry Road, Cincinnati, Ohio.**

Shaker Sieve

The sieve platform in this low cost dynamic sieve shaker is rotated in a circular arc and swayed in a vertical arc simultaneously. It is used for field, laboratory and production sieving or grading operations on soils, sand, gravel, aggregates, chemical powders, plastics, powdered metal, small parts, bearings and similar granular or powdery substances. **Soiltest, Inc., 4711 West North Avenue, Chicago 39, Illinois.**




Steel Beam Joint

A construction technique uses a 6-inch lightweight structural steel member as an expansion joint between concrete paving sections. The beam is used as a screed to strike off the concrete without having to wait for one section to set before pouring the next. The method is said to give a smoother floor. **Jones & Laughlin Steel Corporation, 3 Gateway Center, Pittsburgh 30, Pennsylvania.**

Utility Pump

This new utility pump incorporates a defuser priming system that permits rapid priming with a minimum of water in the pump case. A cover plate may be removed for inspection. It has tapped holes for vacuum and pressure gauges and a drain plug. Discharge outlet can be changed to any of three positions. **Marlow Pumps, Division of Bell & Gossett, Midland Park, New Jersey.**



CONCRETE CONSTRUCTION

literature

FREE copies of these items may be obtained by mailing the reader cards facing page 16.

Plastic form liners. Lustreform No. 2900 is a specially compounded plastic available in flat sheets or shaped to contours as desired. Super-smooth, high lustre concrete panels are produced through its use, and it is especially effective in color work. It is available from reliable distributor-fabricators, shaped to specified design. Described in a brochure No. 57-3. United States Rubber Company, 2638 North Pulaski Road, Chicago 39, Illinois.

Bulletin on testing. The first issue of "The Testing World" has just been published. This is a monthly paper available without charge to any reader interested in receiving it. It is devoted to descriptions of testing apparatus and techniques, as well as to general information about the concrete industry. Soiltest, Inc., 4711 West North Avenue, Chicago 39, Illinois.

Conveyor. Leaflet 357M tells the story of the Faircrete concrete conveyor in placing concrete. Two men can move concrete from transit-mix truck to form, delivering at any desired rate and discharging at heights up to 26 feet. The belt rides on 4-inch triple-troughing idlers fitted with ball bearings that lessen friction wear and material spillage. The machine is designed with self-cleaning features, travels easily behind a truck. While it is tailor-made for concrete, it can be used for handling other materials. The Fairfield Engineering Company, Marion, Ohio.

Chemicals for concrete. A catalog presents descriptions of Sika Chemical Corporation admixtures, joint sealers, coatings and maintenance materials. The book is arranged with file index cards for easy reference to the proper product for any use, and complete descriptions, specifications and installation instructions are given for each. A profusion of graphs, photographs and diagrams accompany the material presented in the catalog, making it a valuable handbook for concrete construction work. Sika Chemical Corporation, Passaic, New Jersey.

strong

& rugged..

fast & safe

One quick look at the Challenge Instant Trowel, side by side with ANY competitive machine, is all you need to prove it is the strongest, most rugged machine on the market. Compare the rugged dual handle; ¾" stationary guard ring; the extra strong spider plate with 1" hex bars — the 1¼" main shaft is the largest in the industry

The Challenge operates at 145 RPM and completes the job in much less time. It is as much as 50% faster than some machines.

ON DISPLAY in Chicago
NRMCA Feb. 10-13
CONCRETE EXP. Feb. 24-26

COOK BROS.

**CHALLENGE
INSTANT TROWEL**

COMBINATION
FLOATING & FINISHING
MACHINE

36" and 48" Models



Finger tip controls are conveniently located for safe, easy operation and assure positive set blade adjustment and engine speed. Mercury safety shut-off switch is another extra safety feature.

Action Test The Challenge Instant Trowel For '58

COOK BROS. EQUIPMENT CO.
Exclusive World Wide Distributor For The Challenge Instant Trowel
3334 San Fernando Road • Los Angeles 65 • Telephone CLinton 6-3151

STEEL STAKES by dee

**SLASH COSTS on:
Flat Work, Curbs
Footings, Bracing**

**STOP
THIS
WASTE**

- ▶ Solid Steel Stakes . . . Always drive straight in any type of ground
- ▶ 12 Nail Holes, 1 inch on center allows nailing at any point
- ▶ Will not twist or bend
- ▶ Set up and strip 10 times faster
- ▶ Easiest to pull out
- ▶ No clean-up after stripping
- ▶ Can be used 100 times or more

**Save Material and Labor
Make More Money**



dee Concrete Products Co.

670 N. Michigan Ave., Chicago 11, ILL.

NOW YOU CAN PAY-AS-YOU-BUILD



New, modern power equipment like Pumps, Power Trowels, Transit Levels — can be yours to USE while you pay for it out of the extra profits it helps you produce! And you get...

UP TO 12 MONTHS TO PAY!



FREE!

Full details on the new Pay-As-You-Build plan that lets you pay for new power equipment while it makes profits for you! Send for your free copy of this booklet! Write today!



TOOL COMPANY
1958 Walnut Street
Kansas City 8, Mo.



GATES FORMING SYSTEMS ARE FAST

You can erect and strip up to 50% faster with Gates.

HERE'S WHY:

- Waling and bracing are reduced to an absolute minimum.
- Corner hinges are the only hardware used; no special tying devices needed.
- Plywood panels are lightweight—easily handled by one man; quickly transported from job to job.

There's a fast, low-cost Gates System for every forming job.



Write for detailed information.

Gates & Sons, Inc.
80 South Galapago Denver 23, Colorado

equipment tools and materials

Additional free information concerning these items may be obtained by mailing the reader service cards in the center spread of this issue.





Trailer Hoist

Erection costs are eliminated and trucking problems reduced by the use of this tilt-up tower and hoist combination. Erection time for the standard 35-foot tower is two minutes. Additional sections may be added. The entire unit trails readily behind any pick-up truck on its own pneumatic-tired wheels. **Thomas Hoist Company, 20 S. Hoyne Avenue, Chicago 12, Illinois.**

Backfill Tamper

With an overall length of 107½ inches, this tamper is particularly suitable for preparing holes when setting utility poles. The crescent shaped butt is designed to fit utility work and provides easy "walking." The throttle valve has a lock-on clip to permit use of the tool while backfilling the pole at the surface. **Portable Compressor and Contractors' Tools Division, Worthington Corporation, Holyoke, Massachusetts.**




Pump for Repellents

A unique pump is available for applying silicone water repellents to any masonry structure. It can be used by contractors and building maintenance men for applying silicone type water repellents above ground to brick, concrete, concrete block, cinder block and sandstone, as well as pitch base coatings below grade before backfills are made. **The Campbell-Hausfield Company, Harrison, Ohio.**

Power Trowel

A low-cost, 18-pound, 20-inch trowel takes advantage of friction and speed in place of weight for concrete finishing. Blades telescope for finishing flush with curbs. The unit collapses for carrying in car trunk. It finishes 2000 square feet per hour, working stiff, dry mixes not workable by hand. **Goldblatt Tool Company, 1910 Walnut Street, Kansas City 8, Missouri.**




CONCRETE CONSTRUCTION

equipment

tools

materials

Additional free information concerning any item described in these columns may be obtained by filling




out and mailing the postage-free reader service cards which may be found in the center spread of this issue.

Vibrator Blades

These 17-pound Sabre blades come in varying lengths and attach readily to Dart vibrators. Operating up to 10,000 rpm at high cycle or 14,000 rpm at 60 cycle, the slender blades offer full force, amplitude and frequency for close work in prestressed concrete or in any restricted area where normal vibrators cannot do the job. Sabre blade action eliminates bubbles along sides, gives better concrete bond. Blades are easily removed for normal submersion use of the vibrator. **Dart Manufacturing and Sales Company, 1002 South Jason Street, Denver, Colorado.**

Form Board

The incombustible, fibrous glass form board being installed by this workman serves as a permanent form for poured-in-place light weight roof decks, as an attractive interior ceiling, as an acoustical ceiling and as roof insulation. It is available in various sizes and in thicknesses to meet specific thermal requirements. Three types are manufactured: a deluxe product with a white Fiberglas mat facing, a type for industrial users and an economy type for concealed areas. **Owens-Corning Fiberglas Corporation, Toledo 1, Ohio.**




NEW Hi Carbon Alloy Steel Stake

Bracing
Footings
Curbs
Gutters

12, 18, 24, 30, 36
and 42 inch lengths.



Stake can be placed
flat against lumber
for secure nailing.



SYMONS CLAMP & MFG. CO.
4271 Diversey Ave., Chicago 39, Ill., Dept. B-8
We will be glad to send contractors a
sample 12" stake if request is received on
company letterhead. Please include 50c
to cover cost of postage and handling.
OFFER LIMITED!

Name.....

Firm.....

Address.....

City.....Zone.....State.....


perfectly cured and hardened CONCRETE at a cost savings with DEMICON Cure Hard

One application of DEMICON Cure-Hard to
freshly poured concrete surfaces will give
you:

a perfect membrane that retains
moisture and prevents cracking

a dust-free, chemical-resistant,
hardened surface

a cost savings—material
applied for less than 1c
per square foot



McMILLAN FLOOR PRODUCTS CO.

2045 East Eight Mile Road Hazel Park, Michigan

For FREE Information write direct or use Reader Service Cards

ECONOMY offers 3 FORM SERVICES

FOR CONCRETE CONSTRUCTION

① **EPCO Steel Forms.** Available on a purchase basis for a wide range of form requirements. Free form erection drawings are supplied.

② **ECONOMY Steel Forms.** Rental forms for larger, more difficult and unusual form requirements. Supplied with supervisory service.

③ **SPECIAL ECONOMY Forms.** Custom-built forms on a purchase basis for your special forming needs. Included are forms for:

PRECAST PRESTRESSED CONCRETE




ECONOMY FORMS CORP.

FOR CATALOG and full address of nearest office, write Economy Forms Corp., Box 128-I, Des Moines, Iowa.

OFFICES IN: Kansas City, Mo.; Lincoln, Neb.; Minneapolis, Minn.; Ft. Wayne, Ind.; Milwaukee, Wis.; Cleveland, Ohio; Columbus, Ohio; Metuchen, N. J.; Rochester, N. Y.; Springfield, Mass.; Waltham, Mass.; Washington, D. C.; Decatur, Ga.; Charlotte, N. C.; Dallas, Texas; Tulsa, Okla.; Houston, Texas; Los Angeles, Cal.; Oakland, Cal.; Denver, Colo.

Bonds NEW to OLD concrete
—less than 4¢ per square foot!



GOOD EXAMPLE: Granville St. Bridge, Vancouver, British Columbia. One of largest 8 lane bridges in North America. Here Weld-Crete, the amazing, patented, job-proved liquid bonding agent, was applied to bridge surface to bond cement dividing strips. GENRL CONTR., Dominion Bridge Company. Now, over 4 years later, bonds are as good as new.

Weld-Crete *permanently* bonds new concrete, or cement plaster, *directly* to old concrete . . . or to any other structurally sound surface no matter how smooth! No costly, time-taking surface preparation. Just apply, let dry, and pour or trowel new concrete. Ideal for new construction, remodeling, repairs . . . ramps, floors, precast shapes, driveways, highways, walls, machine mounts and pads. Get fact-packed literature from your Weld-Crete Dealer, see Sweets File, or write us direct.

LARSEN PRODUCTS CORP., BOX 57565, BETHESDA, MD.

literature

Compactor. The Kelley Compactor Power Float is said to produce superior wear-resistant floors, driveways, ramps, runways and walks with real savings in time and materials. This portable machine and its use on both monolithic and double course floors is described in detail in Bulletin K-101. Kelley Machine Division, Wiesner-Rapp Company, Inc., 285 Hinman Avenue, Buffalo 23, New York.

Compressor. Hydrovane Rotary Compressors are presented in Bulletin No. E-268. Among features stressed is accessibility for inspection or repair, and reduction in number of working parts. Illustrations include cut-a-way photos taken from directly below the unit and sectional views of each side. Component parts are also shown. Davey Compressor Company, Kent, Ohio.

FREE copies of these items may be obtained by mailing the reader cards facing page 16.

Foaming agent. A booklet contains charts and graphs derived from research conducted at the University of Michigan Engineering Research Institute on Elastizell, a liquid chemical which is used as a basis for making strong, lightweight, insulating, moisture-resistant concretes of many uses from sand, cement, water and air. With Elastizell complete control is possible over such physical properties as density, weight, strength and insulating value—and also over cost. Stocking various aggregates is unnecessary for Elastizell-type concrete incorporates all the advantages found in today's diverse aggregate market and eliminates the complexities involved in choosing a specific lightweight aggregate for a specific application. Booklet 2gEL is available from Elastizell Corporation of America, 815 West Miller Street, Alpena, Michigan.

INDEX TO ADVERTISERS

Autolene Lubricants Co.	17
Beaver-Advance Corp.	25
Colorado Fuel & Iron Corp.	inside back cover
Columbia-Southern Chemical Corp.	12
Concrete Transport Mixer Co.	inside front cover
Cook Bros. Equipment Company	29
Dee Concrete Products Company	29
Economy Forms Corporation	32
Gates & Sons, Inc.	30
Goldblatt Tool Company	30
Harnischfeger Corporation	3
Kelley Machine Division	2
Larsen Products Company	32
The Master Builders Company	back cover
McMillan Products Company	31
New Monarch Machine and Stamping Co.	21
Patent Scaffolding Co., Inc.	22
Sika Chemical Corporation	28
Simplex Forms System, Inc.	27
Solvay Process Division	15
Spanall of the Americas	8
Symons Clamp & Manufacturing Co.	16 & 31
Viber Company	23

a-
m
y
a-
al
g
s-
es
r.
is
es
n-
st.
s-
n-
in
nd
ed
ht
on.
ri-
est

17
25
ver
12
ver
29
29
32
30
30
3
2
32
ver
31
21
22
28
27
15
8
31
23
ION